

1. Does all the Fencing even what is along the southeast boundary go?

Yes, all remaining fencing will leave the site.

2. Does the Hill beyond the fencing go?

Yes, the hill is actually the former foundation of the building. Contains a slab and concrete block foundation walls, and some soil.

3. Will the contractor need to do a layout of the excavation, hire a surveyor?

No, ATC will layout the excavation limits

4. Are we removing the trees?

Yes, the trees will need to be removed to access the soils in the storm water basin.

5. Will the hole be filled (storm water basin)?

No the site will be returned to existing grade.

6. Will the concrete be hauled away?

Yes, all concrete, slabs from the former building will be removed from the site.

7. Do you have a plan for the railroad ties? Or an approval for recycling?

No. Contractor is responsible for removing the railroad spurs and disposal offsite.

8. What is being done with the storm drain piping?

The storm drain needs to be removed and disposed of. It is PVC pipe connected to storm water basin.

9. Will we level the berm along the northern property line by the storage sheds?

No just remove the fence, leave the berm.

10. Should we assume all concrete is non-haz and can be sent to a recycler, or does it need to go to Landfill?

Concrete can be recycled.

11. Will there be any addendums?

No just answers to questions.

12. Do I need to provide testing soil cost?

No ATC will conduct testing of the soil on the excavation floor and sidewalls.

13. What certification do I need?

All workers will be required to have OSHA 40-HAZWOPER in compliance with 29 CFR 1910.120

14. Can the backfill quantity be changed to tons vs cubic yards?

No please keep the estimated backfill at cubic yards.

15. Can bids be submitted through email to Lisa Johnson?

Yes bids must be received by Lisa Johnson either email [clerk@cityofgrayling.org](mailto:clerk@cityofgrayling.org) ; or via mail P.O. Box 549, Grayling, MI 49738; or delivered to 1020 City Boulevard, Grayling, MI 49738.

16. Can you confirm the bid is due on June 30th at 2PM?

Yes Bids are Due June 30<sup>th</sup> at 2:00 PM (1400 hours)

17. What if the quantity is over 7,300 tons of soil removal? Will contractor be responsible for excavation charge?

We do not anticipate more than 7,300 tons of soil to be removed. This is not a full site cleanup

18. Can you tell what the restoration requirements are?

Site will be returned to existing grade with suitable backfill as specified in the Bid document.